Vulcan Fire Salvage Skyline Stewardship Agreement

Georgetown Ranger District
Eldorado National Forest

Unit	Logging System	Acres	Status	Biomass Cut/Skid/ Yard	Masticate	Machine Pile
1	Mech	25	Green	25	25	--
2	Mech	34	Green	--	--	--
3	Mech	20	Green	--	--	--
4	Mech	3	Green	3	--	3
5	Mech	11	Salvage	--	--	11
5a	Mech	6	Green	--	6	--
5b	Mech	10	Green	--	10	--
6	Mech	3	Green	--	3	--
7	Mech	10	Salvage	--	--	10
7a	Mech	6	Salvage	--	--	6
7b	Mech	5	Salvage	--	--	5
8	Mech	69	Green	--	--	--
9	Mech	6	Green	--	--	--
14	Mech	12	Salvage	--	--	12
14a	Mech	4	Salvage	--	--	--
15	Mech	11	Salvage	--	--	11
15a	Mech	4	Salvage	--	--	--
16	Mech	1	Salvage	--	--	1
16a	Mech	1	Salvage	--	--	1
17	Mech	39	Green	--	39	--
18	Mech	38	Green	38	--	38
18a	Mech	2	Green	2	--	2
19	Mech	23	Green	23	--	23
20	Mech	3	Green	--	3	--
21	Mech	9	Green	--	9	--
21a	Mech	6	Green	6	6	--
22	Mech	23	Green	--	23	--
23	Mech	13	Salvage	--	--	13
24	Mech	34	Green	34	34	--
24a	Mech	19	Salvage	--	--	19
25	Mech	8	Green	--	--	--
26	Mech	8	Green	--	--	--
27	Mech	7	Green	--	--	--
28	Mech	30	Green	--	--	--
29	Mech	42	Green	--	--	--
30	Mech	7	Green	--	--	--
34	Mech	13	Salvage	--	13	--
36	Mech	10	Salvage	--	--	10
38	Sky	5	Salvage	5	--	--
39	Mech	32	Green	--	--	--
39a	Mech	6	Green	--	--	--
39b	Mech	7	Green	--	--	--
40	Mech	8	Green	--	--	--
47	Mech	10	Green	10	10	--
47a	Mech	6	Green	6	6	--
90	Sky	21	Salvage	21	--	--
91	Sky	13	Salvage	13	--	--
91-D	Sky	7	Salvage	7	--	--
92	Sky	16	Salvage	16	--	--
92a	Sky	4	Salvage	4	--	--
93	Sky	33	Salvage	33	--	--
93a	Sky	6	Salvage	6	--	--
94	Sky	12	Salvage	12	--	--
95	Sky	15	Salvage	15	--	--
96	Sky	22	Salvage	22	--	--
97	Sky	2	Salvage	2	--	--
97a	Sky	3	Salvage	3	--	--
98	Sky	12	Salvage	12	--	--
P-1	none	8	Green	--	--	8
P-2	none	1	Green	--	--	1
Total		**824**		**318**	**187**	**174**

T13 N R11 E

- Sale Area/Subdivision Boundary, F.1
- Unburned Harvest Unit, Mech, Individual Marked Trees, F.5, F.8-c, F.12
- Burned Harvest Unit - Mechanical, DxD, F.5, F.8-e, F.12
- Burned Harvest Unit - Skyline Yarding, DxD, F.5, F.8-e, F.12 SY
- System Roads - F.12, G.2, G.2.3
- 14N35 — Restricted Road Use, F.18
- Proposed Temporary Roads - F.8-a, G.2.4, G.2.5.1
- Protection of Improvements (trail), G.1
- System Road Reconstruction to be completed in another contract, F.1.3
- Mandatory Stewardship Road Reconstruction, F.5, G.2, G.2.1, G.2.2
- Mandatory Stewardship Road Construction, F.5, G.2, G.2.1, G.2.2
- Protection of Improvements - Transmission line, G.1
- Protection of Improvements - Picnic Area, G.1
- LOP for Terrestrial Wildlife - Between **March 1 and August 15**, F.13
- Protection Measures for Wildlife- LOP portion of Unit 39, 39a, 39b between **February 1 thru Septemberl 30**, F.13
- Units 92, 95, 96, 98 — LOP for Plant Surveys - No harvest related work prior to July 1, 2023, Refer to project operations schedule, F.13
- Enitre Project Area — LOP - No Harvest Permitted prior to 0600 am in any operating day within 500 ft of occupied residence, refer to project operations schedule, F.13
- Other Ownership, G.1
- Streamcourse Buffer Strip - (equipment exclusion), 100' from either side unless otherwise agreed, Perennial Stream, G.1
- Streamcourse Buffer Strip - (equipment exclusion), 50' from either side unless otherwise agreed, Seasonal Stream, G.1
- Streamcourse Buffer Strip - (equipment exclusion), 25' from either side unless otherwise agreed, Ephemeral Stream, G.1
- Site Specific Protection Measures - **For sale advertisement only. F.13, G.1, Actual site locations are not shown on this map**
- Site Specific Protection Measures - Botanical Site F.13, G.1
- Site Specific Protection Measures - Noxious Weeds, F.13, G.1
- Protection of Improvements - Gates, G1, G2
- Protection of Land Survey Monuments - G.1
- Protection of Improvements - Mine Shaft, Unit 19, G.1
- x–x–x–x — Protection of Improvements -Fence, Unit 19, G.1
- D — Disposal Site - Landing Slash associated with units 91, 91d, and 94, B, F.15
- W — Water Source - Georgetown Public Utility District Hydrant (GPUD), F.17.1
- DF & Limbing — Felling, Bucking and Limbing - All Harvest Units, F.11
- TRAC, SUSP, SPACE, ENDL, — Skidding and Yarding - All Harvest Units, F.12
- Remove — Applies to landings associated with units 91, 91d, 94 and on Road 14N35NSR3, F.15
- MH — Mechanical Harvest - F.12
- BKB — Backblading skid roads and temporary roads within 100' of Volcanoville and Wentworth Springs Road (ELD 63 and ELD64), B
- WHOLE — Whole Tree Yarding and Skidding - All Harvest Units, F.11
- PAL — Forest Wide Average of Forest Service Weather Stations, G.4

Special Note

This map is for advetisement purposes only. The protected CA-1 sites in the legend above are not shown on this map. A revised map showing protected CA-1 areas will be produced upon award of the contract.

0 2,000 Feet

Contours at 40' Intervals
Property Lines Are Approximate

N